

POOL DEMOLITION/BACKFILLING

REQUIREMENTS

PERMIT NO: _____ **APPROVED:** _____ **DATE:** _____

- 1. ALL PLUMBING SHALL BE DISCONNECTED AND CAPPED OFF IN A SAFE AND PROPER MANNER. PERMIT REQUIRED.**
- 2. ALL ELECTRICAL WIRING SHALL BE REMOVED AND CONDUIT ENDS SEALED. PERMIT REQUIRED.**
- 3. THE BOTTOM OF THE POOL SHALL HAVE TWO (2) 3 FOOT BY 3 FOOT HOLES BROKEN THROUGH, ONE IN THE DEEP END AND ONE IN SHALLOW END.**
- 4. THE POOL WALL/BOND BEAM SHALL BE DEMOLISHED A MINIMUM OF 12 INCHES BELOW THE PROPOSED FINISHED GRADE.**
- 5. BACKFILL WITH CLEAN MATERIAL AND COMPACT TO 90% GRADE FOR PROPER DRAINAGE.**
- 6. PROVIDE SOD, GRASS, OR OTHER LANDSCAPE [PERMIT REQUIRED IF WORK EXCEEDS \$1000].**

INSPECTION REQUIREMENTS

- 1. THE FIRST INSPECTION SHALL BE SCHEDULED WHEN THE HOLES IN THE POOL BOTTOM ARE COMPLETE, THE WALL/BOND BEAM IS CUT DOWN AND BEFORE THE BACKFILL BEGINS.**
- 2. SCHEDULE A FINAL INSPECTION FOR PLUMBING, ELECTRICAL AND BUILDING (DEMO) WHEN ALL WORK IS COMPLETE.**